

Summerland Oil Field Onshore Becker Well Update



**Steve Curran, Petroleum Drilling Engineer
California State Lands Commission**

December 19, 2015

Summary

- Summerland Onshore Becker Well Site Map
- Permits Required
- Investigation and Assessment Activity
- Current Status



Becker Pier

Becker Onshore Well

Treadwell Pier

Permits and Plans

- California Coastal Commission (CCC)
 - De Minimus Waiver
- State Water Quality Control Board (SWQCB)
- Army Corps of Engineers (ACOE)
- Santa Barbara County Planning (SBCP)
 - County Department of Parks and Recreation
- Oil Spill Contingency Plan (CSLC)
 - Reviewed by USCG and OSPR

Investigation and Assessment

- Use County Beach (North) Access Road Through Lookout Park and Move Onto Beach
- Excavate Onshore Becker Well Site at Low Tide Cycle
- Uncover Well Casing Take Measurements and GPS
- Assess Condition of Exposed Well Casing
- Mark, Stake and Set Buoy at Well Casing Location
- Take Action to Contain and Clean Up any Oil Seepage
- Return Site to Previous Condition

Staging and Well Site Low Tide



Staging at Lookout Park

Well Site Low Tide



Building The Berm

Berm Containment
Around Well Site





Initial Dig On Well Site

Well Bubbling After Initial Dig



Becker Onshore Well Exposed



Well Casing Marked



Casing Covered & Marked



Buoy Marking Well Casing at High Tide



Current Status

- Excavation completed on 10/29/2015
- DGS approved Engineering Abandonment Plan Amendment on 11/25/15
- Plan to be completed early February 2016
- Application for Ocean Protection Proposition 1 Grant Funding not accepted, pending CEQA completion; to be resubmitted in two years
- Commission approval granted April 5th to begin CEQA
- CEQA completion, contractor selection and abandonment

