

1 **2.0 PROJECT DESCRIPTION**

2 **2.1 ENVIRONMENTAL SETTING**

3 **2.1.1 Geographic Setting**


4 The SONGS Unit 1 site is located in southern California, approximately 60 miles (97
5 km) south of Los Angeles, 50 miles (80 km) north of San Diego, and 5 miles (8 km)
6 south of downtown San Clemente (Figure 2-1). SONGS Unit 1 is immediately west of
7 Interstate 5 (I-5) in a coastal setting adjacent to the Pacific Ocean on the northern
8 portion of MCB Camp Pendleton. The onshore Unit 1 power plant includes an 11-acre
9 parcel developed by the Applicant under a lease with MCB Camp Pendleton. The
10 Applicant has a separate Agreement with the CSLC (PRC 3193.1) for a 7.5-acre (3-ha)
11 area in the nearshore and offshore areas for a 100-foot-wide (30.5-m) right-of-way
12 easement that extends southwest from the mean lower low water (MLLW) line at the
13 SONGS Unit 1 site to approximately 3,200 feet (975 m) offshore (see Figure 2-2).

14 Including Units 2 and 3, the SONGS power plant and related electrical transmission
15 lines are prominent features in the coastal setting of MCB Camp Pendleton. However,
16 the offshore cooling water conduits that are the subject of this EIR are buried beneath
17 the seafloor and are not visible in the coastal environment from either the shoreline or
18 the ocean surface. The only project features visible in the local setting are the buoys at
19 the ocean surface that mark the location of each of the terminal structures at the end of
20 the two offshore conduits.

21 **2.1.2 Historic Setting**

22 Many commercial electric power plants have been previously built in California. These
23 facilities were constructed near the Pacific Ocean in proximity to the large volume of
24 ocean water used for cooling. The power plants used oil and/or natural gas to heat
25 water into the steam that drove their turbine-generators, and ocean water was utilized to
26 condense the used steam back into a liquid phase for reuse in the plant. The steam
27 water used in these power plants was self-contained and did not mix with the ocean
28 cooling water.

29 While in operation, the nuclear-powered SONGS Unit 1 power plant also used a self-
30 contained cooling steam-water system that did not mix with ocean water. The power
31 plant pumped cool ocean water from the offshore intake conduit into a large heat
32 exchanger, where the steam used to turn the turbine-generator was condensed back
33 into a liquid phase for recirculation through the plant. Spent cooling water was
34 discharged through the second offshore conduit.



**Figure 2-1
Regional Location Map**



No Scale




Figure 2-2
SONGS and Offshore Lease Area

1 **2.2 EXISTING STRUCTURES AND FACILITIES**

2 The SONGS Unit 1 intake and discharge conduits are constructed of 12-foot-diameter
3 (3.7-m), steel-reinforced concrete pipe. The two parallel offshore cooling water conduits
4 are 20 feet apart (6 m), with the longer intake conduit located to the north of the
5 discharge conduit. The offshore conduits extend horizontally from the onshore plant
6 site approximately 3,200 feet (975 m) (intake) and 2,600 feet (762 m) (discharge)
7 southwest of SONGS Unit 1. The offshore portion of each conduit is buried beneath the
8 ocean bottom and is covered with approximately 4 feet (1.2 m) of sand, with the
9 conduits following the local ocean bottom profile.

10 A terminal structure has been constructed at the west end of both the intake and
11 discharge conduits. The terminal structures rest on separate foundations that extend
12 approximately 30 feet (9 m) beneath the ocean bottom and are surrounded by 4 feet
13 (1.2 m) of rock cover at the ocean floor (Figures 2-3 and 2-4). The intake structure is
14 located in water approximately 27 feet (8.2 m) deep, and it rises vertically to
15 approximately 15.5 feet (4.7 m) above the ocean floor, or approximately 11 feet (3.3 m)
16 below the surface of the ocean. Its outside horizontal dimensions are 20 by 27.5 feet
17 (6.1 by 8.2 m). The discharge conduit terminal structure is located in water
18 approximately 25 feet (7.6 m) deep, and it rises vertically to approximately 11 feet
19 (3.3 m), or approximately 14 feet (4.3 m) below the ocean surface. Because these
20 structures create a potential navigational hazard, buoys are maintained at each
21 structure to mark the locations for boaters.

22 Each terminal structure consists of nine rectangular, stacked, reinforced concrete
23 sections (or modules), with reinforced concrete columns at each of the four corners of
24 the structure (Figure 2-4). The prefabricated concrete modules measure between 3.8
25 and 5.5 feet (1.2 m and 1.7 m) in height. A 12-inch-thick (30-cm) velocity cap rests on
26 eight columns approximately 4 feet (1.2 m) above the top of the intake structure.

27 Each conduit also includes manhole risers spaced every 500 feet (152 m): five on the
28 intake conduit and four on the discharge conduit. The manhole risers extend between
29 one and five feet (0.3 and 1.5 m) above the seafloor, and there are no marker buoys for
30 the risers.

31 **2.3 COMPONENTS OF THE PROPOSED PROJECT**

32 The proposed disposition of the offshore cooling water conduits includes the following
33 actions, as described in the Project Application and the Applicant's Work Execution Plan
34 (WEP).




Figure 2-3
Cross Sections of Intake Terminal Structure
(Discharge Structure Identical Except for Velocity Cap)




Figure 2-4
Plan View of Terminal Structure
without Velocity Cap

1 2.3.1 Removal of Terminal Structures

2 The terminal structures would be removed by equipment brought to the offshore site by
3 barge. The marine equipment would be mobilized out of the Port of Long Beach. A
4 barge with an 80-ton crane and clam bucket (Figure 2-5) would be towed to the project
5 site by tugboat. The barge crew and divers would stage out of either Dana Point or
6 Oceanside Harbor and would travel daily to the site on a crew boat. The barge would
7 be anchored at the project site, and it would require several days to lay out the anchor
8 spread in relation to prevailing weather, which generally comes from the northwest. The
9 crane would be used for moving concrete sections of the terminal structures and
10 manhole risers as well as to operate a clamshell bucket for dredging operations.

11 The clamshell dredge operating from the crane barge would be used to expose the
12 perimeter of the terminal structures at the seafloor. Excavated material, including the
13 riprap, would be sidecast away from the structure. Once the crane barge was anchored
14 onsite, the barge crew with diver support would work initially on removal of the
15 discharge terminal structure. Divers would break the connections between the concrete
16 components of the sections. Divers would make the necessary disconnections to free
17 each component, and all concrete components would be lifted clear of the structure.
18 Once the discharge structure was removed, the barge would be moved and reanchored
19 to remove the intake terminal structure and velocity cap.

20 The WEP includes an Anchoring Plan that specifies the plans and protocols that would
21 be employed in deploying, using, and recovering anchorages. The crane barge and
22 support vessels would be moored in three- or four-point anchorages. The *Anchoring*
23 *Plan* is included in this EIR as Appendix D.

24 A diamond wire cutting machine would be used to make vertical cuts in the top three
25 sections of the terminal structures to sever each of the concrete sections from the four
26 corner columns. Divers would break the connections between the velocity cap and its
27 support columns, and the riser sections. Each concrete section would be removed by a
28 crane operating from the barge, and the velocity cap, columns, and concrete sections
29 removed from the structure would be placed on the seafloor bottom by the crane. A
30 prefabricated metal mammal barrier would be placed in the opening of each of the
31 terminal structures; openings in the barriers would allow gradual backfilling with sand
32 and prevent entry into the conduits by marine mammals or recreational divers.

33 When both terminal structures have been dismantled and all other offshore disposition
34 activities have been completed, the crane would remove the concrete sections from the
35




Figure 2-5
Typical Crane Barge

1 seafloor and place them on a deck barge towed to the site from the Port of Long Beach
2 by a tugboat. This would eliminate the need for a deck barge remaining at the site for
3 the entire four-month duration of the offshore disposition activities.

4 **2.3.2 Removal of Buoys**

5 Surface buoys have been placed at the two terminal structures to mark the location of
6 these potential navigational hazards. With the removal of the terminal structures, the
7 maintenance of the marker buoys and anchor blocks would no longer be necessary,
8 and they would be removed.


9 **2.3.3 Removal of Manhole Risers**

10 In addition to removing the terminal structures, the Proposed Project would remove the
11 nine manhole risers. The removal of the manhole risers would take place in two marine
12 environments, nearshore surfzone and offshore. Each marine environment requires a
13 removal methodology unique to that environment. Each methodology is described
14 below, and the manhole risers are depicted in Figure 2-6.


15 **Nearshore Surfzone Removal**

16 Four manhole risers are located nearshore in water depths insufficient for floating
17 vessel support, where anchoring of support vessels would be undesirable. A skid
18 based surf sled vehicle (SSV), consisting of a steel pipe structure atop skids with a
19 working platform on top of the steel pipe columns, would be used to access the
20 nearshore surfzone manhole risers (Figure 2-7). The SSV would be launched from the
21 crane barge anchored offshore and set on the sand within the conduit corridor. The
22 SSV would support a dive team working from its deck. A pull winch would be anchored
23 on the beach to pull the SSV shoreward, guided by a cable from a deck winch located
24 on the crane barge (Figure 2-8). SSV and beach winch anchoring procedures are
25 described in *Anchoring Plan* (Appendix D).

26 Starting with the manhole riser located closest to shore, the SSV would be fastened to
27 the seafloor with pin piles installed by high pressure water jets to a depth of
28 approximately 4 feet (1.2 m). A cofferdam would be lowered over the manhole riser to
29 create a safe working environment for the divers. Dive teams would remove both the
30 cover plate from the top of the manhole riser and the manhole port at the top of the
31 conduit. The cover plate and manhole port would be lifted onto the deck of the SSV. A
32 prefabricated mammal barrier would then be installed in the manhole opening in the top
33 of the conduit. The divers would excavate around the manhole riser base using
34



SECTIONAL VIEW
TYPICAL EXISTING RISER STRUCTURE



SECTIONAL VIEW
TYPICAL RISER STRUCTURE FINAL DISPOSITION



Figure 2-6
Manhole Risers



Figure 2-7
Surf Sled Vehicle (SSV)




Figure 2-8
SSV Beach Winch

1 handheld airlifts and cut the straps that hold the riser to the top of the conduit. The riser
2 would be pulled offshore through the sand corridor to the crane barge utilizing a pulling
3 wire. The SSV would then be pulled offshore to the next manhole location. The
4 manhole risers would be removed along the intake conduit first, and then along the
5 discharge conduit.

6 **Offshore Removal**

7 There are five offshore manhole risers located in water depths sufficient for support
8 from floating vessels. The crane barge and other equipment used for the removal of the
9 terminal structures would be utilized for the removal of the offshore manhole risers. The
10 SSV and cofferdam would not be needed. The offshore manhole riser removal would
11 follow the same steps and use the same tools described above for the nearshore riser
12 removal.

13 **2.3.4 Duration of Offshore Activities**

14 Removal of the terminal structures and manhole risers is projected to require
15 approximately 4 months. Up to 20 personnel would be required during the offshore
16 phase of the work, including workers on the barge, divers, and boat operators.

17 **2.3.5 Materials Removal**

18 Once the components have been removed from the two terminal structures and the
19 manholes, and other activities that could create debris are complete, the material
20 removal would begin. Materials to be removed would be identified by a sonar survey. A
21 deck barge would be towed to the site, the concrete debris would be removed from the
22 seafloor, lifted onto the deck barge, and secured for transport. A tugboat would tow the
23 deck barge back to the Port of Long Beach. The major concrete components on deck
24 resulting from dismantling the terminal structures would consist of concrete sections
25 from both terminal structures and one velocity cap from the intake structure;
26 additionally, there would also be debris from nine manhole risers. The total cargo load
27 would consist of approximately 600 tons (544 metric tons) of terminal structure
28 components and approximately 60 tons (54 tons) of manhole risers. One or two
29 roundtrips of the deck barge would be required to tow the concrete debris back to port,
30 depending upon the size of the deck barge. The *Sea Floor Debris Removal Plan*, which
31 is part of the WEP, is included in this EIR as Appendix E, and provides additional details
32 about material removal activities.

1 **2.3.6 Materials Processing and Recycling**

2 Materials removed from the site would be barged to the Port of Long Beach for recycling
3 and disposal. Once the deck barge has reached port, the deck load from the barge
4 would be placed on dry ground, and a hydraulic backhoe would reduce the concrete to
5 rubble for transport to a commercial recycler. All recycling activities would be
6 conducted at an approved site within existing permit conditions; recycling activities are
7 therefore not considered to be a part of the Proposed Project and are not addressed in
8 this EIR.

9 **2.3.7 Marine Safety**

10 The Marine Safety Plan (MSP) has been developed to support the proposed project
11 operations. The primary concerns addressed in the MSP are personnel, environmental,
12 and vessel safety. One important element of the MSP is the Critical Operations and
13 Curtailment Plan (COCP), which requires the project manager to shut down or not
14 permit any operation when existing or forecast sea states or weather conditions would
15 create unsafe working conditions for personnel or equipment. The MSP is included in
16 this EIR as Appendix F.

17 **2.3.8 Oil Spill Response Plan**

18 The Oil Spill Response Plan is part of the project WEP, and it specifies procedures and
19 protocols that would be utilized in the event of an onshore or offshore oil spill resulting
20 from proposed project activities. The *Oil Spill Response Plan* is included in this EIR as
21 Appendix G.

22 **2.3.9 Diver's Safety Plan**

23 The Diver's Safety Plan will be part of the project WEP, and it will specify techniques,
24 equipment, and procedures to be used for each underwater operation. The Diver's
25 Safety Plan will include an evacuation plan for injured divers. The plan specifies that all
26 diving operations will comply with U.S. Coast Guard and OSHA safety regulations for
27 commercial diving operations. The *Diver's Safety Plan* is included in this EIR as
28 Appendix H.

29 **2.3.10 Conduit Plugs**

30 The CSLC lease extends offshore from the MLLW line; the portion of the easement that
31 extends to the east above MLLW is leased by the Applicant from MCB Camp
32 Pendleton.

1 This onshore portion of the conduits would be plugged with concrete from MLLW to the
2 existing tsunami gates, inland from the existing seawall. Installation of the concrete
3 plug would be accomplished from the SONGS Unit 1 site through existing manholes on
4 the plant site (Figure 2-9). A plug would be installed by divers, and concrete would be
5 pumped into a series of fabric forms within the conduits to fill the conduits and prevent
6 any future use or failure of the conduits beneath the beach. Installation of the conduit
7 plugs would require a crew of 12 workers, including divers. Project work on this
8 onshore section of the conduits, east of the MLLW line, would only require approval
9 from MCB Camp Pendleton, since it is outside of the jurisdiction of the CSLC.

10 **2.3.11 Potential Future Reuse of Conduits**

11 Under the Proposed Project, the conduits would remain in place and could be used for
12 any future project that could utilize the ocean water intake and discharge structures.
13 During scoping for this EIR, both the Water Authority and MWD indicated that they are
14 considering the feasibility of a regional seawater desalination facility at MCB Camp
15 Pendleton. Such a regional facility would supplement the water supplies of the Water
16 Authority and the MWD, and the fresh water produced at the desalination facility could
17 serve both water districts as well as MCB Camp Pendleton. The Base commented
18 during scoping that it was aware of the consideration being given to a desalination
19 facility at MCB Camp Pendleton, and it supported the Proposed Project and the
20 retention of the offshore conduits in place.


21 Although there are no specific plans for a regional desalination facility at this time, the
22 existing intake and discharge conduits may be suitable for such a potential future use.
23 This EIR, however, does not evaluate a future reuse of the offshore conduits in the
24 impact analysis, since such a proposal is speculative and is not a reasonably
25 foreseeable project at this time.

26 **2.3.12 Lease Termination**

27 The purpose of the Proposed Project is to terminate the existing Lease Agreement and
28 replace it with a Lease Termination/Abandonment Agreement in which the Applicant
29 would remain responsible for the abandoned conduit structures.

30 **2.4 DISPOSITION SCHEDULE**

31 Once the CSLC has certified the Final EIR and approved the Proposed Project, the
32 disposition schedule would depend on the time required for: (1) the CCC to issue a
33 Coastal Development Permit; (2) permitting by other agencies; (3) National
34



**Figure 2-9
Conduit Plug**

1 Environmental Policy Act (NEPA) compliance, if required; and (4) scheduling by the
2 Applicant. It is anticipated that overall activities involving disposition, demolition, and
3 removal and recycling of materials would last for approximately 4 months starting in
4 early 2006. An extended period of inclement weather or unsafe sea states could extend
5 the project duration, as described in Section 2.3.7 and Appendix F.

6 **2.5 ENVIRONMENTAL COMPLIANCE INSPECTION AND MITIGATION**
7 **MONITORING**

8 The CSLC will adopt a Mitigation Monitoring Program (MMP) to ensure the
9 implementation of all mitigation measures contained in the Final EIR. Section 6 of this
10 EIR contains the MMP for the Proposed Project.

1
2
3
4
5
6
7
8
9

This page intentionally left blank.